Project Name: Old Sharpe's Lane (South of 401)

Department: Public Works

Type of Project: Road Construction

Basis for Activity: Asset Renewal

Description:

Reconstruction of a 100m road plus 30m cul-de-sac.

Work includes excavation of existing deteriorated roadway, fabric overlay, 4 inches A gravel, 8 inches B gravel for road and 12 inches B gravel for cul-de-sac and 50mm asphalt.

Strategic Plan Relationship(s):

Priority #2 – Financial Plan (efficiently updating infrastructure assets and initiating a preventative maintenance program)

Rationale:

This road is in extremely bad condition which results in additional wear and tear on equipment when performing winter control. Although there is only access to two driveways, the existing state consists of stagnant water and nearly no drainage ability.

Staff Contact: Steve Cassidy

Project Finances

		Actuals	Budget						
Description		Expensed to Current Year	Total Project	Prior Approved	2024	2025	2026	2027	2028
313 - Capital	Expense		52000		52000				