Project Name:

Crystal Road

Department:

Public Works

Type of Project:

Roads Construction

Basis for Activity:

Asset Renewal

Description:

Reconstruction of 1500m of Crystal Road.

Work includes pulverization, fabric overlay, 4 inches A gravel, 8 inches B gravel and finished with tar and chip.

Strategic Plan Relationship(s):

Priority #2 - Financial Plan (efficiently updating infrastructure assets and

initiating a preventative maintenance program)

Rationale:

This road is in extremely bad condition and is heavily travelled on as a thruroad. Tar and chip is being recommended due to its close proximity to Kinch Street which was completed with success in 2023.

Staff Contact: Steve Cassidy

Project Finances

		Actuals	Budget						
Description		Expensed to Current Year	Total Project	Prior Approved	2024	2025	2026	2027	2028
313 - Capital	Expense		208100		208100				